

BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:-Development of Roads and Drains at Kasagattapura, Vaderahalli, Shivakote, Kachohalli Grama Panchayathi Limits and Surrounding Areas of Yelahanka Assembly Constituency Under Amrutha Nagarothana Grants.(PACKAGE NO-05)

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
1	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead 1 By Manual Means B Cement Concrete Grade M-15 & M-20 (PWD SR 2021-22 Vol III Pg no 8 Item No 2.7(i))								
	Drain Bottom Raft								
	Vaderahalli Village								
	2nd Cross Road 10th A Main Road	Cum	2	56.00	0.75	0.15	12.60		
	Drain Side Wall								
	Vaderahalli Village								
	2nd Cross Road 10th A Main Road	Cum	4	56.00	0.15	0.60	20.16		
	Culvert Bottom Raft								
	Vaderahalli Village								
	6th Cross Road	Cum	1	6.20	1.20	0.23	1.71		
	Basic rate	731.00							
	Area weightage 3%	21.93							
	Sub Total	752.93							
	Total						34.47	752.93	25955.00
2	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead (iii) Dismantling Stone Masonry B Rubble stone masonry in cement mortar. (PWD SR 2021-22 Vol III Pg no 8 Item No 2.10(iv))								
	Culvert								
	Kachohalli Village								
	Manchohalli Main Road To Srinivasa House	Cum	2	8.30	0.45	0.40	2.99		
	Vaderahalli Village								
	6th Cross Road	Cum	2	6.20	0.45	0.50	2.79		
	Basic rate	481.00							
	Area weightage 3%	14.43							
	Sub Total	495.43							
	Total						5.78	495.43	2863.00
	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenances required to complete the work. (PWD SR 2021-22 Vol -I Pg No 5 item no 1.4.1)								
	New Drain	Cum							
	Kachohalli Village								
	Jayanna House Road								
	LHS	Cum	1	82.00	1.10	1.10	99.22		
	Seenappa House To Nice Road Compound								
	LHS	Cum	1	115.00	1.10	0.90	113.85		
	Lakshman Gowdru House to Nice Road Bridge								
	Chikkatimmayya Land								
	RHS	Cum	1	116.00	1.10	1.05	133.98		

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	Shankaranarayana Land Through Mudd Ramaiah Land to Main Road	Cum	2	174.00	1.10	1.05	401.94		
	Manchohalli Main Road To Srinivasa House								
	LHS	Cum	1	140.00	1.10	1.05	161.70		
	Mahadeshwara Nagara								
	1st Cross road	Cum	1	82.00	1.10	0.90	81.18		
	For Culvert								
	Shankaranarayana Land Through Mudd Ramaiah Land to Main Road	Cum	1	6.80	1.40	1.10	10.47		
		Cum	1	8.30	1.40	0.95	11.04		
	Manchohalli Main Road To Srinivasa House	Cum	1	8.30	1.40	1.10	12.78		
	Desilt								
	Kachohalli Village								
	Jayanna House Road	Cum	1	82.00	0.60	0.45	22.14		
	Cross Road	Cum	1	1800.00	0.60	0.45	486.00		
	Vaderahalli Village								
	Netaji Layout								
	Main Road	Cum	2	378.00	1.10	1.20	997.92		
	1st Main Road	Cum	2	171.00	1.10	0.90	338.58		
	1st Main, Cross Road 1	Cum	2	63.30	1.10	0.90	125.33		
	1st Main, Cross Road 2	Cum	2	52.80	1.10	0.90	104.54		
	Main Road, Cross Road	Cum	2	37.00	1.10	0.90	73.26		
	Muneshwara Layout								
	7th Cross Road	Cum	2	74.00	0.95	0.90	126.54		
	2nd Cross Road 10th A Main Road	Cum	2	56.00	0.95	0.90	95.76		
	1st Cross Road	Cum	1	54.00	0.95	0.90	46.17		
	Main Road	Cum	2	54.00	0.95	0.90	92.34		
	10th Main 1st Cross Road	Cum	2	56.00	0.95	0.90	95.76		
	Culvert								
	Vaderahalli Village								
	Netaji Layout								
	1st Main Road	Cum	1	6.50	1.40	0.95	8.65		
	1st Main, Cross Road 1	Cum	1	5.20	1.40	0.95	6.92		
	1st Main, Cross Road 2	Cum	1	5.20	1.40	0.95	6.92		
	Main Road, Cross Road	Cum	1	5.60	1.40	0.95	7.45		
	Muneshwara Layout					0.15			
	5th Cross Road	Cum	1	5.90	1.40	0.95	7.85		
	6th Cross Road	Cum	1	6.20	1.40	0.95	8.25		
	7th Cross Road	Cum	1	6.10	1.40	0.95	8.11		
	Desilt								
	Vaderahalli Village								
	8th Cross Road	Cum	2	82.00	0.45	0.45	33.21		
	For Flagging Course								
	Vaderahalli Village								
	8th Cross Road	Cum	2	82.00	0.15	0.15	3.69		
	Cross Road	Cum	1	1300.00	0.60	0.45	351.00		
	Shivakaote								
	Muthugadha Halli								
	Lingadahalli Main Road								

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	LHS Shivakote	Cum	1	52.00	1.10	1.20	68.64		
	Opposite Shivakote Grama Panchayat Office	Cum	2	82.50	1.10	1.20	217.80		
	Shivakote Main Road	Cum	1	60.20	1.10	1.20	79.46		
	Anjanappa House to Anjanadri School								
	LHS	Cum	1	210.00	0.95	0.90	179.55		
	For Culvert								
	Shivakote								
	Muthugadha Halli								
	Shaneshwara Swamy Temple Surrounding	Cum	1	9.20	1.40	0.95	12.24		
	Lingadahalli Main Road								
	LHS	Cum	1	7.00	1.40	0.95	9.31		
	Lingadahalli Main Road to Ramaiah House	Cum	1	8.40	1.40	0.95	11.17		
		Cum	1	6.20	1.40	0.95	8.25		
	Kasagattapura								
	Ishwara Temple Surrounding	Cum	1	28.00	0.80	0.60	13.44		
	Soldevanahalli								
	Gopal Layout Mahalakshmi Layout								
	Gopal Layout Main Road								
	LHS	Cum	1	202.10	1.10	1.20	266.77		
	1st Main Road								
	RHS	Cum	1	167.00	1.10	0.90	165.33		
	Basava Shri Layout								
	Cross Road 1	Cum	2	112.00	1.10	0.90	221.76		
	Achit Nagara								
	Cross Road								
	LHS	Cum	1	68.00	1.10	0.90	67.32		
	For Culvert								
	Kasagattapura								
	Soldevanahalli								
	1st Main Road	Cum	1	6.20	1.40	0.95	8.25		
	Desilt								
	Kasagattapura								
	Muddinapalya Lake Road	Cum	2	254.00	0.45	0.45	102.87		
	Soldevanahalli								
	Gopal Layout Mahalakshmi Layout								
	Gopal Layout Main Road								
	RHS	Cum	1	202.10	0.45	0.45	40.93		
	1st Main Road								
	Basava Shri Layout								
	Cross Road 3	Cum	2	78.00	0.45	0.45	31.59		
	Cross Road 4	Cum	2	79.00	0.45	0.45	32.00		
	Cross Road	Cum	1	350.00	0.60	0.50	105.00		
	Achit Nagara								
	Main Road	Cum	2	412.00	0.45	0.45	166.86		

SI No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	Foundation for lighting poles	Cum	200.00	0.80	0.80	1.65	211.20		
	Veerasagara SSM Drain								
		Cum	1	19.80	3.85	1.95	148.65		
	Basic rate	186.00							
	Area weightage 3%	5.58							
	Sub Total	191.58							
	Total						6240.92	191.58	1195635.00
4	Providing and laying in position plain cement concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (PWD SR 2021-22 Vol -I Pg 15 item no 2.1.3)								
	For Drain	Cum							
	Kachohalli Village								
	Jayanna House Road								
	LHS	Cum	1	82.00	1.10	0.15	13.53		
	Seenappa House To Nice Road Compound								
	LHS	Cum	1	115.00	1.10	0.15	18.98		
	Lakshman Gowdru House to Nice Road Bridge Chikkatimmayya Land								
	RHS	Cum	1	116.00	1.10	0.15	19.14		
	Shankaranarayana Land Through Mudd Ramaiah Land to Main Road	Cum	2	174.00	1.10	0.15	57.42		
	Manchohalli Main Road To Srinivasa House								
	LHS	Cum	1	140.00	1.10	0.15	23.10		
	Mahadeshwara Nagara								
	Ist Cross road	Cum	1	82.00	1.10	0.15	13.53		
	Vaderahalli Village								
	Netaji Layout								
	Main Road	Cum	2	378.00	1.10	0.15	124.74		
	Ist Main Road	Cum	2	171.00	1.10	0.15	56.43		
	Ist Main, Cross Road 1	Cum	2	63.30	1.10	0.15	20.89		
	Ist Main, Cross Road 2	Cum	2	52.80	1.10	0.15	17.42		
	Main Road, Cross Road	Cum	2	37.00	1.10	0.15	12.21		
	Muneshwara Layout								
	7th Cross Road	Cum	2	74.00	0.95	0.15	21.09		
	2nd Cross Road 10th A Main Road	Cum	2	56.00	0.95	0.15	15.96		
	Ist Cross Road	Cum	1	54.00	0.95	0.15	7.70		
	Main Road	Cum	2	54.00	0.95	0.15	15.39		
	10th Main Ist Cross Road	Cum	2	56.00	0.95	0.15	15.96		
	Shivakaote								
	Muthugadha Halli								
	Lingadahalli Main Road								
	LHS	Cum	1	52.00	1.10	0.15	8.58		
	Shivakote								
	Opposite Shivakote Grama Panchayat Office	Cum	2	82.50	1.10	0.15	27.23		
	Shivakote Main Road	Cum	1	60.20	1.10	0.15	9.93		
	Anjanappa House to Anjanadri School								
	LHS	Cum	1	210.00	0.95	0.15	29.93		

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	Kasagattapura								
	Ishwara Temple Surrounding	Cum	1	28.00	0.80	0.15	3.36		
	Soldevanahalli								
	Gopal Layout Mahalakshmi Layout								
	Gopal Layout Main Road								
	LHS	Cum	1	202.10	1.10	0.15	33.35		
	1st Main Road								
	RHS	Cum	1	167.00	1.10	0.15	27.56		
	Basava Shri Layout								
	Cross Road 1	Cum	2	112.00	1.10	0.15	36.96		
	Achit Nagara								
	Cross Road								
	LHS	Cum	1	68.00	1.10	0.15	11.22		
	For Culvert								
	Kachohalli Village								
	Shankaranarayana Land Through Mudd Ramaiah Land	Cum	1	6.80	1.40	0.15	1.43		
		Cum	1	8.30	1.40	0.15	1.74		
	Manchohalli Main Road To Srinivasa House	Cum	1	8.30	1.40	0.15	1.74		
	Vaderahalli Village								
	Netaji Layout								
	1st Main Road	Cum	1	6.50	1.40	0.15	1.37		
	1st Main, Cross Road 1	Cum	1	5.20	1.40	0.15	1.09		
	1st Main, Cross Road 2	Cum	1	5.20	1.40	0.15	1.09		
	Main Road, Cross Road	Cum	1	5.60	1.40	0.15	1.18		
	Muneshwara Layout					0.15			
	5th Cross Road	Cum	1	5.90	1.40	0.15	1.24		
	6th Cross Road	Cum	1	6.20	1.40	0.15	1.30		
	7th Cross Road	Cum	1	6.10	1.40	0.15	1.28		
	Shivakaote								
	Muthugadha Halli								
	Shaneshwara Swamy Temple Surrounding	Cum	1	9.20	1.40	0.15	1.93		
	Lingadahalli Main Road								
	LHS	Cum	1	7.00	1.40	0.15	1.47		
	Lingadahalli Main Road to Ramaiah House	Cum	1	8.40	1.40	0.15	1.76		
		Cum	1	6.20	1.40	0.15	1.30		
	Kasagattapura								
	Soldevanahalli								
	1st Main Road	Cum	1	6.20	1.40	0.15	1.30		
	Foundation for lighting poles	Cum	200	0.80	0.80	0.15	19.20		
	Veerasagara								
	SSM Drain	Cum	1	19.80	3.85	0.15	11.43		
	Basic rate	5752.00							
	Area weightage 3%	172.56							
	Sub Total	5924.56							
	Total						693.45	5924.56	4108404.00

SI No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
5	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 (The cost of steel reinforcement & formwork to be paid separately) (PWD SR 2021-22 Vol -I Pg 17 item no 2.4.2)								
	Bottom Raft	Cum							
	Kachohalli Village								
	Jayanna House Road								
	LHS	Cum	1	82.00	0.90	0.15	11.07		
	Seenappa House To Nice Road Compound								
	LHS	Cum	1	115.00	0.90	0.15	15.53		
	Lakshman Gowdru House to Nice Road Bridge Chikkatimmayya Land								
	RHS	Cum	1	116.00	0.90	0.15	15.66		
	Shankaranarayana Land Through Mudd Ramaiah Land to Main Road	Cum	2	174.00	0.90	0.15	46.98		
	Manchohalli Main Road To Srinivasa House								
	LHS	Cum	1	140.00	0.90	0.15	18.90		
	Mahadeshwara Nagara								
	Ist Cross road	Cum	1	82.00	0.90	0.15	11.07		
	Vaderahalli Village								
	Netaji Layout								
	Main Road	Cum	2	378.00	0.90	0.15	102.06		
	Ist Main Road	Cum	2	171.00	0.90	0.15	46.17		
	Ist Main, Cross Road 1	Cum	2	63.30	0.90	0.15	17.09		
	Ist Main, Cross Road 2	Cum	2	52.80	0.90	0.15	14.26		
	Main Road, Cross Road	Cum	2	37.00	0.90	0.15	9.99		
	Muneshwara Layout								
	7th Cross Road	Cum	2	74.00	0.75	0.15	16.65		
	2nd Cross Road 10th A Main Road	Cum	2	56.00	0.75	0.15	12.60		
	Ist Cross Road	Cum	1	54	0.75	0.15	6.08		
	Main Road	Cum	2	54	0.75	0.15	12.15		
	10th Main Ist Cross Road	Cum	2	56.00	0.75	0.15	12.60		
	Shivakaote								
	Muthugadha Halli								
	Lingadahalli Main Road								
	LHS	Cum	1	52.00	0.90	0.15	7.02		
	Shivakote								
	Opposite Shivakote Grama Panchayat Office	Cum	2	82.50	0.90	0.15	22.28		
	Shivakote Main Road	Cum	1	60.20	0.90	0.15	8.13		
	Anjanappa House to Anjanadri School								
	LHS	Cum	1	210.00	0.75	0.15	23.63		
	Kasagattapura								
	Ishwara Temple Surrounding	Cum	1	28.00	0.60	0.15	2.52		
	Soldevanahalli								
	Gopal Layout Mahalakshmi Layout								
	Gopal Layout Main Road								
	LHS	Cum	1	202.10	0.90	0.15	27.28		
	Ist Main Road								

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	RHS	Cum	1	167.00	0.90	0.15	22.55		
	Basava Shri Layout								
	Cross Road 1	Cum	2	112.00	0.90	0.15	30.24		
	Achit Nagara								
	Cross Road								
	LHS	Cum	1	68.00	0.90	0.15	9.18		
	Side Wall								
	Kachohalli Village								
	Jayanna House Road								
	LHS	Cum	2	82.00	0.15	0.75	18.45		
	Seenappa House To Nice Road Compound								
	LHS	Cum	2	115.00	0.15	0.60	20.70		
	Lakshman Gowdru House to Nice Road Bridge								
	RHS	Cum	2	116.00	0.15	0.75	26.10		
	Shankaranarayana Land Through Mudd Ramaiah Land to Main Road	Cum	4	174.00	0.15	0.75	78.30		
	Manchohalli Main Road To Srinivasa House								
	LHS	Cum	2	140.00	0.15	0.75	31.50		
	Mahadeshwara Nagara								
	Ist Cross road	Cum	2	82.00	0.15	0.60	14.76		
	Vaderahalli Village								
	Netaji Layout								
	Main Road	Cum	4	378.00	0.15	0.90	204.12		
	Ist Main Road	Cum	4	171.00	0.15	0.60	61.56		
	Ist Main, Cross Road 1	Cum	4	63.30	0.15	0.60	22.79		
	Ist Main, Cross Road 2	Cum	4	52.80	0.15	0.60	19.01		
	Main Road, Cross Road	Cum	4	37.00	0.15	0.60	13.32		
	Muneshwara Layout								
	7th Cross Road	Cum	4	74.00	0.15	0.60	26.64		
	2nd Cross Road 10th A Main	Cum	4	56.00	0.15	0.60	20.16		
	Ist Cross Road	Cum	2	54.00	0.15	0.60	9.72		
	Main Road	Cum	4	54.00	0.15	0.60	19.44		
	10th Main Ist Cross Road	Cum	4	56.00	0.15	0.60	20.16		
	Shivakaote								
	Muthugadha Halli								
	Lingadahalli Main Road								
	LHS	Cum	2	52.00	0.15	0.90	14.04		
	Shivakote								
	Opposite Shivakote Grama	Cum	4	82.50	0.15	0.90	44.55		
	Shivakote Main Road	Cum	2	60.20	0.15	0.90	16.25		
	Anjanappa House to Anjanadri								
	LHS	Cum	2	210.00	0.15	0.60	37.80		
	Kasagattapura								

SI No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	Ishwara Temple Surrounding	Cum	2	28.00	0.15	0.30	2.52		
	Soldevanahalli								
	Gopal Layout Mahalakshmi								
	Gopal Layout Main Road								
	LHS	Cum	2	202.10	0.15	0.90	54.57		
	1st Main Road								
	RHS	Cum	2	167.00	0.15	0.60	30.06		
	Basava Shri Layout								
	Cross Road 1	Cum	4	112.00	0.15	0.60	40.32		
	Achit Nagara								
	Cross Road								
	LHS	Cum	2	68.00	0.15	0.60	12.24		
	Culvert								
	Bottom Raft	Cum							
	Kachohalli Village								
	Shankaranarayana Land Through Mudd Ramaiah Land to Main Road	Cum	1	6.80	1.20	0.20	1.63		
		Cum	1	8.30	1.20	0.20	1.99		
	Manchohalli Main Road To Srinivasa House	Cum	1	8.30	1.20	0.20	1.99		
	Vaderahalli Village								
	Netaji Layout								
	1st Main Road	Cum	1	6.50	1.20	0.20	1.56		
	1st Main, Cross Road 1	Cum	1	5.20	1.20	0.20	1.25		
	1st Main, Cross Road 2	Cum	1	5.20	1.20	0.20	1.25		
	Main Road, Cross Road	Cum	1	5.60	1.20	0.20	1.34		
	Muneshwara Layout								
	5th Cross Road	Cum	1	5.90	1.20	0.20	1.42		
	6th Cross Road	Cum	1	6.20	1.20	0.20	1.49		
	7th Cross Road	Cum	1	6.10	1.20	0.20	1.46		
	Shivakaote								
	Muthugadha Halli								
	Shaneshwara Swamy Temple Surrounding	Cum	1	9.20	1.20	0.20	2.21		
	Lingadahalli Main Road								
	LHS	Cum	1	7.00	1.20	0.20	1.68		
	Lingadahalli Main Road to Ramaiah House	Cum	1	8.40	1.20	0.20	2.02		
		Cum	1	6.20	1.20	0.20	1.49		
	Kasagattapura								
	Soldevanahalli								
	1st Main Road	Cum	1	6.20	1.20	0.20	1.49		
	Side Wall								
	Kachohalli Village								

SI No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	Shankaranarayana Land Through Mudd Ramaiah Land to Main Road	Cum	2	6.80	0.25	0.75	2.55		
		Cum	2	8.30	0.25	0.60	2.49		
	Manchohalli Main Road To Srinivasa House	Cum	2	8.30	0.25	0.75	3.11		
	Vaderahalli Village								
	1st Main Road	Cum	2	6.50	0.25	0.60	1.95		
	1st Main, Cross Road 1	Cum	2	5.20	0.25	0.60	1.56		
	1st Main, Cross Road 2	Cum	2	5.20	0.25	0.60	1.56		
	Main Road, Cross Road	Cum	2	5.60	0.25	0.60	1.68		
	Muneshwara Layout								
	5th Cross Road	Cum	2	5.90	0.25	0.60	1.77		
	6th Cross Road	Cum	2	6.20	0.25	0.60	1.86		
	7th Cross Road	Cum	2	6.10	0.25	0.60	1.83		
	Shivakaote								
	Muthugadha Halli								
	Shaneshwara Swamy Temple Surrounding	Cum	2	9.20	0.25	0.60	2.76		
	Lingadahalli Main Road								
	LHS	Cum	2	7.00	0.25	0.60	2.10		
	Lingadahalli Main Road to	Cum	2	8.40	0.25	0.60	2.52		
		Cum	2	6.20	0.25	0.60	1.86		
	Kasagattapura								
	Soldevanahalli								
	1st Main Road	Cum	2	6.20	0.25	0.60	1.86		
	Foundation for lighting poles	Cum	200.00	0.70	0.70	1.50	147.00		
	Bed Concrete								
	Kachohalli Village								
	Cross Road	Cum	1.00	1800.00	0.60	0.15	162.00		
	Vaderahalli Village								
	8th Cross Road	Cum	2	82.00	0.45	0.15	11.07		
	Cross Road	Cum	1	1300.00	0.45	0.15	87.75		
	Kasagattapura								
	Cross Road	Cum	1	350.00	0.60	0.15	31.50		
	Basic rate	6256.00							
	Add 5% for Shuttering	312.80							
		6568.80							
	Area weightage 3%	197.06							
	Sub Total	6765.86							
	Total						1875.79	6765.86	12691313.00
6	Supplying, Fitting and Placing TMT Fe550 bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications. MORTH Specification NO.1600&2200 (PWD SR 2021-22 Vol -III Pg 99 item no 13.1)								

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	For Drain	Cum					1380.74		
		kg	Steel assumed 60Kg/Cum of Concrete				82844.37		
	For Culvert	tonne					82.84		
		Cum					55.73		
		kg	Steel assumed 90 Kg/Cum of Concrete				5015.39		
		tonne					5.02		
	For Road	Cum					321.00		
		kg	Steel assumed 12Kg/Cum of Concrete				3852.00		
		tonne					3.85		
	Foundation for lighting poles	Cum					147.00		
		kg	Steel assumed 100Kg/Cum of Concrete				14700.00		
		tonne					14.70		
	Basic rate	103329.00							
	Area weightage 3%	3099.87							
	Sub Total	106428.87							
	Total						106.41	106428.87	11325283.00
7	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand) (PWD SR 2021-22 Vol -II Pg 9 item no 5.4)								
	Kasagattapura								
	Veerasagara								
	SSM Drain								
		Cum	2	19.80	0.55	1.80	39.20		
	Basic rate	5422.00							
	Area weightage 3%	162.66							
	Sub Total	5584.66							
	Total						39.20	5584.66	218942.00
8	Providing and Fixing pre cast covering Slab 100mm thick made out of CC , Jelly 20mm Down Size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete as per Engineer incharge. (Data Rate)								
	Kachohalli Village								
	Jayanna House Road								
	LHS	Sqm	1	82.00	0.90		73.80		
	Seenappa House To Nice Road Compound								
	LHS	Sqm	1	115.00	0.90		103.50		
	Lakshman Gowdru House to Nice Road Bridge Chikkatimmayya Land								
	RHS	Sqm	1	116.00	0.90		104.40		
	Shankaranarayana Land Through Mudd Ramaiah Land to Main Road	Sqm	2	174.00	0.90		313.20		
	Manchohalli Main Road To Srinivasa House								
	LHS	Sqm	1	140.00	0.90		126.00		
	Mahadeshwara Nagara								
	1st Cross road	Sqm	1	82.00	0.90		73.80		
	Cross Road	Sqm	1	1800.00	0.90		1620.00		
	Vaderahalli Village								
	Netaji Layout								
	Main Road	Sqm	2	378.00	0.90		680.40		
	1st Main Road	Sqm	2	171.00	0.90		307.80		
	1st Main, Cross Road 1	Sqm	2	63.30	0.90		113.94		
	1st Main, Cross Road 2	Sqm	2	52.80	0.90		95.04		
	Main Road, Cross Road	Sqm	2	37.00	0.90		66.60		

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	Muneshwara Layout								
	7th Cross Road								
	8th Cross Road	Sqm	2	74.00	0.75		111.00		
	2nd Cross Road 10th A Main	Sqm	2	82.00	0.75		123.00		
	1st Cross Road	Sqm	2	56.00	0.75		84.00		
	Main Road	Sqm	1	54.00	0.75		40.50		
	10th Main 1st Cross Road	Sqm	2	54.00	0.75		81.00		
	Cross Road	Sqm	2	56.00	0.75		84.00		
		Sqm	1	1300.00	0.90		1170.00		
	Shivakaote								
	Muthugadha Halli								
	Lingadahalli Main Road								
	LHS	Sqm	1	52.00	0.90		46.80		
	Shivakote								
	Opposite Shivakote Grama Panchayat Office	Sqm	2	82.50	0.90		148.50		
	Shivakote Main Road	Sqm	1	60.20	0.90		54.18		
	Anjanappa House to Anjanadri School								
	LHS	Sqm	1	210.00	0.75		157.50		
	Kasagattapura								
	Soldevanahalli								
	Gopal Layout Mahalakshmi Layout								
	Gopal Layout Main Road								
	LHS	Sqm	1	202.10	0.90		181.89		
	1st Main Road								
	RHS	Sqm	1	167.00	0.90		150.30		
	Basava Shri Layout								
	Cross Road 1	Sqm	2	112.00	0.90		201.60		
	Cross Road	Sqm	1	350.00	0.90		315.00		
	Achit Nagara								
	Cross Road								
	LHS	Sqm	1	68.00	0.90		61.20		
	Data rate	2072.00							
	Total						6688.95	2072.00	13859505.00
9	Providing and Fixing pre cast covering Slab 230mm thick made out of CC , Jelly 20mm Down Size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete as per Engineer incharge. (Data Rate)								
	Culvert cover Slab	Sqm							
	Kachohalli Village								
	Shankaranarayana Land Through Mudd Ramaiah Land	Sqm	1	6.80	1.20		8.16		
		Sqm	1	8.30	1.20		9.96		
	Manchohalli Main Road To Srinivasa House	Sqm	1	8.30	1.20		9.96		
	Vaderahalli Village								
	Netaji Layout								
	1st Main Road	Sqm	1	6.50	1.20		7.80		
	1st Main. Cross Road 1	Sqm	1	5.20	1.20		6.24		
	1st Main. Cross Road 2	Sqm	1	5.20	1.20		6.24		
	Main Road. Cross Road	Sqm	1	5.60	1.20		6.72		
	Muneshwara Layout								
	5th Cross Road	Sqm	1	5.90	1.20		7.08		

SI No	Description of work	Unit	Measurement			Qty	Rate	Amount
			No.	L	B	D		
	6th Cross Road	Sqm	1	6.20	1.20		7.44	
	7th Cross Road	Sqm	1	6.10	1.20		7.32	
	Shivakaote							
	Muthugadha Halli							
	Shaneshwara Swamy Temple Surrounding	Sqm	1	9.20	1.20		11.04	
	Lingadahalli Main Road							
	LHS	Sqm	1	7.00	1.20		8.40	
	Lingadahalli Main Road to Ramaiah House	Sqm	1	8.40	1.20		10.08	
		Sqm	1	6.20	1.20		7.44	
	Kasagattapura							
	Veterinary Hospital	Sqm	1	5.30	1.50		7.95	
	Soldevanahalli							
	1st Main Road	Sqm	1	6.20	1.20		7.44	
	Data rate	5037.00						
	Total					129.27	5037.00	651133.00
10	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) Mix 1:2:4 (M15) Using 20 mm nominal size graded crushed coarse aggregates (PWD SR 21-22 Vol I Pg no 17 Item No 2.4.1)							
	Flagging Coarse PCC	Cum						
	Kachohalli Village							
	Jayanna House Road							
	RHS	Cum	1	82.00	0.15	0.15	1.85	
	Vaderahalli Village							
	8th Cross Road	Cum	2	82.00	0.15	0.10	2.46	
	Cross Road	Cum	1	1300.00	0.15	0.10	19.50	
	Kasagattapura							
	Veerasagara							
	SSM Bed Concrete	Cum						
		Cum	1	19.80	2.55	0.15	7.57	
	Copping Concrete							
	Kachohalli Village							
	Jayanna House Road							
	RHS	Cum	2	82.00	0.15	0.10	2.46	
	Cross Road	Cum	2	1800.00	0.15	0.10	54.00	
	Vaderahalli Village							
	8th Cross Road	Cum	4	82.00	0.15	0.10	4.92	
	Cross Road	Cum	2	1300.00	0.15	0.10	39.00	
	Kasagattapura							
	Soldevanahalli							
	Cross Road	Cum	2	350.00	0.15	0.10	10.50	
	Kerb PCC							
	Kachohalli Village							
	Country Club Road	Cum	2	214.00	0.20	0.10	8.56	

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	Vaderahalli Village								
	Netaji Layout								
	Main Road	Sqm	2	378.00		0.35	264.60		
	Muneshwara Layout								
	5th Cross Road	Sqm	2	42.00		0.35	29.40		
	6th Cross Road	Sqm	1	70.00		0.35	24.50		
	7th Cross Road	Sqm	2	74.00		0.35	51.80		
	8th Cross Road	Sqm	2	82.00		0.35	57.40		
	2nd Cross Road 10th A Main Road	Sqm	2	56.00		0.35	39.20		
	1st Cross Road	Sqm	1	54.00		0.35	18.90		
	Main Road	Sqm	2	54.00		0.35	37.80		
	10th Main 1st Cross Road	Sqm	2	56.00		0.35	39.20		
	Kasagattapura								
	Soldevanahalli								
	Achit Nagara								
	Main Road	Sqm	4	412.00		0.35	576.80		
	Basic rate	85.00							
	Area weightage 3%	2.55							
	Sub Total	87.55							
	Total						1289.40	87.55	112887.00
13	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications. (PWD SR 2021-22 Vol -II Pg 17 item no 6.33)								
	Flagging coarse	Sqm							
	Jayanna House Road								
	RHS	Sqm	2	82.00		0.40	65.60		
	Cross Road	Sqm	2	1800.00		0.20	720.00		
	Vaderahalli Village								
	8th Cross Road	Sqm	4	82.00		0.20	65.60		
	Cross Road	Sqm	1	1300.00		0.20	260.00		
	Kasagattapura								
	Cross Road	Sqm	2	350.00		0.20	140.00		
	Basic rate	1067.00							
	Area weightage 3%	32.01							
	Sub Total	1099.01							
	Total						1251.20	1099.01	1375082.00
14	Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work. In all kinds of soils upto 300 mm depth, (PWD SR 21-22 Vol I Pg no 8 Item No 1.12)								
	New Road	Cum							
	Kachohalli Village								
	Jayanna House Road	Cum	1	82.00	5.90	0.30	145.14		
	Seenappa House To Nice Road Compound	Cum	1	115.00	5.50	0.30	189.75		

SI No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	Soldevanahalli								
	Gopal Layout Mahalakshmi Layout								
	Gopal Layout Main Road	Cum	1	202.10	4.50	0.30	272.84		
	Basava Shri Layout								
	Cross Road 1	Cum	1	112.00	5.10	0.30	171.36		
	Cross Road 3	Cum	1	78.00	5.20	0.30	121.68		
	Cross Road 4	Cum	1	79.00	5.10	0.30	120.87		
	Achit Nagara								
	Main Road	Cum	2	412.00	4.50	0.30	1112.40		
	Cross Road	Cum	6	10.00	3.50	0.30	63.00		
		Cum	1	68.00	4.20	0.30	85.68		
	Chik Byalakere								
	Nandi Layout, Cross Road	Cum	1	51.00	5.50	0.30	84.15		
	Gowramma House Road	Cum	1	93.00	5.00	0.30	139.50		
	Cross Road	Cum	1	45.20	5.00	0.30	67.80		
	Basic rate	65.00							
	Area weightage 3%	1.95							
	Sub Total	66.95							
	Total						8872.22	66.95	593996.00
15	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separately MORTH Specification No. 202(PWD SR 2021-22 Vol -III P.No.10 - I.No.2.19)								
	Kasagattapura								
	Muddinapalya Lake Road	Cum	1	54.00	5.30	0.20	57.24		
	Basic rate	422.00							
	Area weightage 3%	12.66							
	Sub Total	434.66							
	Total						57.24	434.66	24880.00
16	Construction of Embankment by excavating the available approved Gravel/Murum deposited at a place or borrow pits during or prior excavation with all lifts and lead, transportation to site, spreading, grading to required slope and compacting to meet the requirement complete as per specifications, including cost of labour, rolling, water, all materials, usage & all other appurtenances required to complete the work. (PWD SR 21-22 Vol I Pg no 7 Item No 1.8)								
	Kachohalli Village								
	Manchohalli Main Road To LHS	Cum	1	140.00	0.60	0.60	50.40		
	Vaderahalli Village								
	Netaji Layout								
	Main Road	Cum	2	378.00	0.60	0.60	272.16		
	Kasagattapura								
	Soldevanahalli								
	For Drain								
	Gopal Layout Mahalakshmi								
	Gopal Layout Main Road								
	LHS	Cum	1	202.10	0.60	0.60	72.76		
	1st Main Road								
	RHS	Cum	1	167.00	0.60	0.30	30.06		
	Basic rate	402.00							
	Area weightage 3%	12.06							
	Sub Total	414.06							
	Total						425.38	414.06	176132.00

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
17	Construction of Granular Sub-Base of required grading as per design mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401 (For Grading -V Material) (PWD SR 21-22 Vol III Pg no 19 Item No 4.1 A (v))								
	For New Road	Cum							
	Kachohalli Village								
	Jayanna House Road	Cum	1	82.00	5.90	0.15	72.57		
	Seenappa House To Nice Road Compound	Cum	1	115.00	5.50	0.15	94.88		
	Lakshman Gowdru House to Nice Road Bridge	Cum	1	116.00	5.80	0.15	100.92		
	Chikkatimmayya Land								
	Shankaranarayana Land								
	Through Mudd Ramaiah Land to Main Road	Cum	1	174.00	7.00	0.15	182.70		
	Manchohalli Main Road To Srinivasa House	Cum	1	140.00	8.00	0.15	168.00		
	Jai Maruthi Layout								
	Main Road	Cum	1	649.00	6.50	0.15	632.78		
	Mahadeshwara Nagara								
	1st Cross road	Cum	1	82.00	6.00	0.15	73.80		
	Ashraya Layout								
	Country Club Road	Cum	1	214.00	10.00	0.15	321.00		
	Vaderahalli Village								
	Netaji Layout								
	1st Main Road	Cum	1	171.00	6.10	0.15	156.47		
	1st Main, Cross Road 1	Cum	1	63.30	4.30	0.15	40.83		
	1st Main, Cross Road 2	Cum	1	52.80	4.30	0.15	34.06		
	Main Road, Cross Road	Cum	1	37.00	4.80	0.15	26.64		
	Muneshwara Layout								
	5th Cross Road	Cum	1	42.00	5.70	0.15	35.91		
	6th Cross Road	Cum	1	70.00	6.00	0.15	63.00		
	7th Cross Road	Cum	1	74.00	5.70	0.15	63.27		
	2nd Cross Road 10th A Main Road	Cum	1	56.00	6.00	0.15	50.40		
	1st Cross Road	Cum	1	54.00	6.10	0.15	49.41		
	Main Road	Cum	1	54.00	6.70	0.15	54.27		
	10th Main 1st Cross Road	Cum	1	56.00	5.90	0.15	49.56		
	Shivakaote								
	Mavalipura								
	Mavalipura Main Road to Survey No.8	Cum	1	212.00	8.40	0.15	267.12		
	Muthugadha Halli								
	Shaneshwara Swamy Temple Surrounding	Cum	1	17.00	15.00	0.15	38.25		
		Cum	1	18.50	4.00	0.15	11.10		
		Cum	1	17.00	4.00	0.15	10.20		
		Cum	1	18.50	4.00	0.15	11.10		
	Lingadahalli Main Road	Cum	1	163.00	5.30	0.15	129.59		
	Ramesh House Road	Cum	1	70.00	5.50	0.15	57.75		
	Handi Muneshwara Temple Road	Cum	1	133.00	5.20	0.15	103.74		
	Shivakote								
	Opposite Shivakote Grama Panchayat Office	Cum	1	82.50	7.00	0.15	86.63		
	Anjanappa House to Anjanadri School	Cum	1	139.30	3.00	0.15	62.69		
	Kasagattapura								
	Kempapura								
	Ishwara Temple Surrounding	Cum	1	10.80	6.80	0.15	11.02		

SI No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
		Cum	1	14.60	13.20	0.15	28.91		
		Cum	1	8.20	3.40	0.15	4.18		
		Cum	1	4.60	3.90	0.15	2.69		
		Cum	1	8.10	2.60	0.15	3.16		
	Muddinapalya Lake Road	Cum	1	6.50	5.50	0.15	5.36		
		Cum	1	200.00	6.50	0.15	195.00		
	Soldevanahalli								
	Gopal Layout Mahalakshmi Layout								
	Gopal Layout Main Road	Cum	1	202.10	4.50	0.15	136.42		
	Basava Shri Layout								
	Cross Road 1	Cum	1	112.00	5.10	0.15	85.68		
	Cross Road 3	Cum	1	78.00	5.20	0.15	60.84		
	Cross Road 4	Cum	1	79.00	5.10	0.15	60.44		
	Achit Nagara								
	Main Road	Cum	2	412.00	4.50	0.15	556.20		
		Cum	6	10.00	3.50	0.15	31.50		
	Cross Road	Cum	1	68.00	4.20	0.15	42.84		
	Chik Byalakere								
	Nandi Layout, Cross Road	Cum	1	51.00	5.50	0.15	42.08		
	Gowramma House Road	Cum	1	93.00	5.00	0.15	69.75		
	Cross Road	Cum	1	45.20	5.00	0.15	33.90		
	Basic rate	2347.00							
	Area weightage 3%	70.41							
	Sub Total	2417.41							
	Total						4418.56	2417.41	10681473.00

- 18 Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:4:8(M5) Using 40 mm nominal size graded crushed coarse aggregates (PWD SR 2021-22 Vol -I P.No.15 - I.No.2.1.2)

New CC Road									
Kachohalli Village									
Jayanna House Road	Cum	1	82.00	5.90	0.15	72.57			
Seenappa House To Nice Road Compound	Cum	1	115.00	5.50	0.15	94.88			
Lakshman Gowdru House to Nice Road Bridge	Cum	1	116.00	5.80	0.15	100.92			
Chikkatimmayya Land									
Shankaranarayana Land									
Through Mudd Ramaiah Land to Main Road	Cum	1	174.00	7.00	0.15	182.70			
Manchohalli Main Road To Srinivasa House	Cum	1	140.00	8.00	0.15	168.00			
Jai Maruthi Layout									
Main Road	Cum	1	649.00	6.50	0.15	632.78			
Mahadeshwara Nagara									
1st Cross road	Cum	1	82.00	6.00	0.15	73.80			
Ashraya Layout									
Country Club Road	Cum	1	214.00	10.00	0.15	321.00			
Vaderahalli Village									
Netaji Layout									
1st Main Road	Cum	1	171.00	6.10	0.15	156.47			
1st Main, Cross Road 1	Cum	1	63.30	4.30	0.15	40.83			
1st Main, Cross Road 2	Cum	1	52.80	4.30	0.15	34.06			

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	Sub Total								
	Total	5524.92					4975.21	5524.92	27487640.00
19	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, primer, sealant, curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete MORTH Specification No.1501 . as per the directions of the Engineer-in-charge of the work. (PWD SR 2021-22 Vol -III Pg 138 item no 20.29)								
	New CC Road								
	Kachohalli Village								
	Jayanna House Road	Cum	1	82.00	5.90	0.15	72.57		
	Seenappa House To Nice Road Compound	Cum	1	115.00	5.50	0.15	94.88		
	Lakshman Gowdru House to Nice Road Bridge	Cum	1	116.00	5.80	0.15	100.92		
	Chikkatimmayya Land								
	Shankaranarayana Land								
	Through Mudd Ramaiah Land to Main Road	Cum	1	174.00	7.00	0.15	182.70		
	Manchohalli Main Road To Srinivasa House	Cum	1	140.00	8.00	0.15	168.00		
	Jai Maruthi Layout								
	Main Road	Cum	1	649.00	6.50	0.15	632.78		
	Mahadeshwara Nagara								
	1st Cross road	Cum	1	82.00	6.00	0.15	73.80		
	Ashraya Layout								
	Country Club Road	Cum	1	214.00	10.00	0.15	321.00		
	Vaderahalli Village								
	Netaji Layout								
	1st Main Road	Cum	1	171.00	6.10	0.15	156.47		
	1st Main, Cross Road 1	Cum	1	63.30	4.30	0.15	40.83		
	1st Main, Cross Road 2	Cum	1	52.80	4.30	0.15	34.06		
	Main Road, Cross Road	Cum	1	37.00	4.80	0.15	26.64		
	Muneshwara Layout								
	5th Cross Road	Cum	1	42.00	5.70	0.15	35.91		
	6th Cross Road	Cum	1	70.00	6.00	0.15	63.00		
	7th Cross Road	Cum	1	74.00	5.70	0.15	63.27		
	2nd Cross Road 10th A Main Road	Cum	1	56.00	6.00	0.15	50.40		
	1st Cross Road	Cum	1	54.00	6.10	0.15	49.41		
	Main Road	Cum	1	54.00	6.70	0.15	54.27		
	10th Main 1st Cross Road	Cum	1	56.00	5.90	0.15	49.56		
	Shivakaote								
	Mavalipura								
	Mavalipura Main Road to Survey No.8	Cum	1	612.00	8.40	0.15	771.12		
	Muthugadha Halli								
	Shaneshwara Swamy Temple Surrounding	Cum	1	17.00	15.00	0.15	38.25		
		Cum	1	18.50	4.00	0.15	11.10		
		Cum	1	17.00	4.00	0.15	10.20		
		Cum	1	18.50	4.00	0.15	11.10		
	Lingadahalli Main Road	Cum	1	163.00	5.30	0.15	129.59		
	Ramesh House Road	Cum	1	70.00	5.50	0.15	57.75		
	Handi Muneshwara Temple Road	Cum	1	133.00	5.20	0.15	103.74		
	Shivakote								

SI No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	Opposite Shivakote Grama Panchayat Office	Cum	1	82.50	7.00	0.15	86.63		
	Anjanappa House to Anjanadri School	Cum	1	139.30	3.00	0.15	62.69		
Kasagattapura									
Kempapura									
	Ishwara Temple Surrounding	Cum	1	10.80	6.80	0.15	11.02		
		Cum	1	14.60	13.20	0.15	28.91		
		Cum	1	8.20	3.40	0.15	4.18		
		Cum	1	4.60	3.90	0.15	2.69		
		Cum	1	8.10	2.60	0.15	3.16		
		Cum	1	6.50	5.50	0.15	5.36		
	Muddinapalya Lake Road	Cum	1	254.00	6.50	0.15	247.65		
Soldevanahalli									
Gopal Layout Mahalakshmi Layout									
	Gopal Layout Main Road	Cum	1	202.10	4.50	0.15	136.42		
Basava Shri Layout									
	Cross Road 1	Cum	1	112.00	5.10	0.15	85.68		
	Cross Road 3	Cum	1	78.00	5.20	0.15	60.84		
	Cross Road 4	Cum	1	79.00	5.10	0.15	60.44		
Achit Nagara									
	Main Road	Cum	2	412.00	4.50	0.15	556.20		
		Cum	6	10.00	3.50	0.15	31.50		
	Cross Road	Cum	1	68.00	4.20	0.15	42.84		
Chik Byalakere									
	Nandi Layout, Cross Road	Cum	1	51.00	5.50	0.15	42.08		
	Gowramma House Road	Cum	1	93.00	5.00	0.15	69.75		
	Cross Road	Cum	1	45.20	5.00	0.15	33.90		
	Basic rate	6837.00							
	Area weightage 3%	205.11							
	Sub Total	7042.11							
	Total						4975.21	7042.11	35035980.00
20	Cutting transverse contraction joints 3 to 4 mm wide and depth 60mm in concrete slab using concrete cutting machine with diamond studded saw within 48 hours of casting of bay / slab etc. complete including subsequent widening of the groove 8 to 10 mm. wide at top having depth of 15 mm. as directed by Engineer incharge. MORTH Specification No. 602.6.3(PWD SR 2021-22 Vol -III Pg 146 item no 4)								
	Kachohalli Village								
	Transverse Cutting	m	393.00	6.40			2515.20		
	Longitudinal Cutting	m	1	1572.00			1572.00		
	Vaderahalli Village								
	Transverse Cutting	m	183	6.00			1098.00		
	Longitudinal Cutting	m	1	577.00			577.00		
	Shivakaote								
	Transverse Cutting	m	318	6.00			1908.00		
	Longitudinal Cutting	m	1	1077.50			1077.50		
Kasagattapura									
	Transverse Cutting	m	365	6.00			2190.00		
	Transverse Cutting	m	1	1429.90			1429.90		

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	Basic rate								
	Area weightage 3%	70.00							
	Sub Total	2.10							
	Total	72.10							
21	Providing to contraction joints polysuphide sealent (Pouring grade) confirming to BS : 5212 - 1989 into sawed groove widened at top for sealent reservoir of specified size and shape as per detailed drawing including fixing Polyethylene foam backer rod of required diameter (approx. 25% larger than the initial 3 mm.to 4 mm. joint) overlaid with bond breaking tape as per detailed drawing. Item includes cleaning the joints with water jet / air compressor and allowing joint to become thoroughly dry before sealent is applied and applying primer. (A) Contraction and longitudinal joints (15 mm. deep x 8mm.wide). MORTH Specification No. 602.6.3(PWD SR 2021-22 Vol -III Pg 147 item no 5)								
	Qty Vide frm Item No-20	m					12367.60		
	Basic rate	165.00							
	Area weightage 3%	4.95							
	Sub Total	169.95							
	Total						12367.60	169.95	2101874.00
22	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum..(Tipper 5.5 m3) (PWD SR 2021-22 Vol-III Page No.3. Item No.1.1A)								
	Qty Vide frm Item No-01+02+03+14+15	Cum					15210.63		
	Total						15210.63	121.54	1848700.00
	Basic rate	118.00							
	Area Weightage 3%	3.54							
	Total	121.54							
23	Cost-of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km (PWD SR 2021-22 Vol-III Page No.3, Item No.1.4A)								
	Qty frm Item No-22	t.Km		15210.63	1.28		19469.60		
	Total						19469.60	98.88	1925155.00
	Basic rate	12.00							
	8Km 12*8	96.00							
	Area Weightage 3%	2.88							
	Total	98.88							
24	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x200x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications. (PWD SR 2021-22 Vol-II Page No.17, Item No.6.32)								
	For Benches Platforms	Sqm	25.00	8.40		0.20	42.00		
	Basic rate	1202.00							
	Area weightage 3%	36.06							
	Sub Total	1238.06							
	Total						42.00	1238.06	51999.00
25	Supplying and filling in plinth with sand under floors, foundation of Bridges including watering, ramming, consolidating and dressing complete. (PWD SR 2021-22 Vol-I Page No.7, Item No.1.11)								
	For Benches Platforms	Cum	25.00	1.80	1.60	0.10	7.20		
	Basic rate	2177.00							
	Area weightage 3%	65.31							
	Sub Total	2242.31							
	Total						7.20	2242.31	16145.00
26	Providing and laying in position Reinforced cement concrete for all Foundation works. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticizers laid in finished layers, well compacted using needle vibrators, including all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour. Usage charges of machinery, curing and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (PWD SR 2021-22 Vol-I Page No.15, Item No.2.2.1.1)								
	For Benches Platforms	Cum	25.00	1.80	1.60	0.10	7.20		

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
	Basic rate	6231.00							
	Area weightage 3%	186.93							
	Sub Total	6417.93							
	Total								
27	Providing, laying & fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, mortar, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. (PWD SR 2021-22 Vol-II Page No.65, Item No.9.40)						7.20	6417.93	46210.00
	For Benches Platforms	Sqm	25.00	2.20	2.00		110.00		
	Basic rate	1139.00							
	Area weightage 3%	34.17							
	Sub Total	1173.17							
	Total								
28	Executive Bench-Made out of Sadarahalli grey granite stone with hand supports with 3 line finishing with arch/plain design with 100mm slabs height 90x Length 1500 width 45cms (1.50*0.45*0.90m) (Including lead and lift Charges) (inclusive of all taxes) As per the director of Engineer Incharge. (Data approved rate)						110.00	1173.17	129049.00
	benches	Nos	25.00				25.00		
	Data Rate	18200.00							
	Total						25.00	18200.00	455000.00
29	Fabricating, supplying and erection of ... ms long hot dip Galvanized Octagonal hot dip Pole with BSEN 10025 grade S 355 JO steel plate for shaft, IS 2062 for base plate with door opening arrangements, including suitable boards, Bakelite sheet and MCBs as per IS specifications suitable to withstand the wind speed of 47 m/s for m Pole in single section and single joint welded as per IS 9595/IS10178AWS having dimensions bottom mm , top..... mm with 3 mm thick, suitable base plate and 4Nos of long J bolts along with template and the Pole shall be hot dip galvanized in single dipping with not less than 65micron as per ASTM-A123 and 153 etc., (excluding foundation) as per drawing appended. 6 m - Top 70 mm and Bottom 130 mm dia (PWD Electrical SR 2021-22 Vol-VI Part-I Page No.7, Item No.4.2.4)								
	Poles for LED Streetlight	Each	200				200.00		
	Basic Rate							10584.00	
	Total						200.00	10584.00	2116800.00
30	Supply of LED Streetlight luminaire with pressure die cast aluminium housing body for optimal thermal dissipation. Lamp compartment comprising of anti glare clear diffuser with Injection moulded polycarbonate material, delivering superior light output Rated life Burning Hrs 50000 hr @ Lumen Maintenance of 70%, maximum light intensity should be between 60 degrees to 70 degrees. CCT > 5500K, IP66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains, Surge Protection- Min 5KV along with Over voltage/ Overload, short circuit/ miss-wiring protection. Compatible for pole mounting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with W System Power consumption. LED Efficiency>130lm/w, nominal CRI >75. Luminaire manufacturer should have in-house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008. Housing with supplier word mark /name shall be Engraved / Embossing on the die cast housing/ Body part. Warranty of 2 Years against any manufacturing defect working under standard electrical conditions as mentioned (PWD Electrical SR 2021-22 Vol-VI Page No.36, Item No.11.8.4)								
	LED Streetlight 90 Watts	No	200				200.00		
	Basic Rate							7777.00	
	Total						200.00	7777.00	1555400.00
31	Geophysical investigation at site for sinking borewells for supplying drinking water to the habitation either through the Hand Pump MWS or P.W.S.S, by vertical electrical sounding by adopting Venner or Schlumbergers's method, including econnaissance survey of geological formation. Geophysical investigation of existing ground water in the vicinity, its quality, quantity and acceptability of the users, indicating the location of the site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 metre in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instruments and accessories to work site, engaging technical personal and labour required etc. NOTE: 1) Additional rate on item 1&2 is allowed for drilling in over burden and fixing Casing pipes beyond 20 M (for fixing Casing pipes only) a) Above 20 M and upto 30 M - 15%, b) Above 30 M - 30% (Measurement of overburden is restricted to the depth of casing pipe fixed excluding initial depth of 20M and projection above ground level). 2) A sum of Rs. 100/- is to be deducted for Dry Borewell towards yield test (PWD SR 2021-22 Vol-V Page No.152, Item No.4)								
		Each BW	4				4	5295.23	21181.00
	Basic Rate	5141.00							

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	3% Area Weightage								
	Total	154.23							
		5295.23							
32	Sinking of Borewell of 165mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burdern upto 20 m. Fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicle, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (Excluding cost of casing pipes, collars, cap etc., complete) (PWD SR 2021-22 Vol-V Page No.151, Item No.1)								
	0-50mtrs	Rmtr	4	50.00			200.00	298.70	59740.00
	Basic Rate	290.00							
	3% Area Weightage	8.70							
	Total	298.70							
33	50-100mtrs(PWD SR 2021-22 Vol-V Page No.151, Item No.1.2)								
		Rmtr	4	50.00			200.00	374.92	74984.00
	Basic Rate	364.00							
	3% Area Weightage	10.92							
	Total	374.92							
34	100-150mtrs (PWD SR 2021-22 Vol-V Page No.151, Item No.1.3)								
		Rmtr	4	50.00			200.00	398.61	79722.00
	Basic Rate	387.00							
	3% Area Weightage	11.61							
	Total	398.61							
35	150-200mtrs (PWD SR 2021-22 Vol-V Page No.151, Item No.1.4)								
		Rmtr	4	50.00			200.00	462.47	92494.00
	Basic Rate	449.00							
	3% Area Weightage	13.47							
	Total	462.47							
36	200-250mtrs (PWD SR 2021-22 Vol-V Page No.151, Item No.1.5)								
		Rmtr	4	50.00			200.00	542.81	108562.00
	Basic Rate	527.00							
	3% Area Weightage	15.81							
	Total	542.81							
37	250-300mtrs (PWD SR 2021-22 Vol-V Page No.151, Item No.1.6)								
		Rmtr	4	50.00			200.00	574.74	114948.00
	Basic Rate	558.00							
	3% Area Weightage	16.74							
	Total	574.74							
38	300-350mtrs (PWD SR 2021-22 Vol-V Page No.151, Item No.1.7)								
		Rmtr	4	50.00			200.00	638.60	127720.00
	Basic Rate	620.00							
	3% Area Weightage	18.60							
	Total	638.60							

Sl No	Description of work	Unit	Measurement				Qty	Rate	Amount
			No.	L	B	D			
39	Supply of ISI mark 175mm nominal bore, plain and steel casing pipe grade of steel Fe 410 of wall thickness conforming to IS 4270-2001 and latest amendments, electrical resistance welded steel tubes, material and conforming to IS 1387-1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5-7m both ends threaded conforming to IS 554-1985 one end fixed with socket conforming to IS 4270-2001 and the other end with screwed pipes all shall be responsibly free from defects. The tubes shall be responsible straight end should be with ISI marking weighing 25.10kg/m. prices include Collar-Medium duty. (PWD SR 2021-22 Vol-V Page No.154, Item No.32)	Rmt	4	60.00			240.00	1990.99	477838.00
	Basic Rate	1933.00							
	3% Area Weightage	57.99							
	Total	1990.99							
40	PVC pipes of 10 Kg/cm ² for 200mm (PWD SR 2021-22 Vol-V Page No.35, Item No.1188)	m	4	10.00			40.00	1329.00	53160.00
41	Providing and laying at site of work MS casing caps as per IS 1239 (part II) 1982 with all latest amendments if any for any dia. The thickness of plate used for covering one end shall be 3mm (minimum). The dimensions of caps and colars shall be strictly as per IS 1239 (Part-II) 1982 with all amendments including cost of material and labour charges for fixing, if any etc. complete with all lead and lifts and as directed by the Engineer in charge (PWD SR 2021-22 Vol-V Page No.155, Item No.34)	Each	4				4	168.92	676.00
	Basic Rate	164.00							
	3% Area Weightage	4.92							
	Total	168.92							
42	Fabricating supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size c/a with necessary cable entry pipe with gland and box should be finished with 7ranks treatment with powder coated paint and finally finished with approved colour etc., complete. (PWD Electrical SR 2022-23 Vol-VI Page No.15, Item No.5.42.2)	Sq.cm	4	1100	20		88000	0.38	33440.00
43	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI Union confirming to IS 1239-II, 1991 with latest amendments if any (PWD SR 2021-22 Vol-V Page No.145, Item No.13.6)	Each	4				4	225.57	903.00
	Basic Rate	219.00							
	3% Area Weightage	6.57							
	Total	225.57							
44	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI hexagonal nipple confirming to IS 1239-II, 1991 with latest amendments if any. (PWD SR 2021-22 Vol-V Page No.146, Item No.15.6)	Each	4	3			12	180.25	2163.00
	Basic Rate	175.00							
	3% Area Weightage	5.25							
	Total	180.25							
45	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI elbow confirming to IS 1239-II, 1991 with latest amendments if any for: (PWD SR 2021-22 Vol-V Page No.144, Item No.7.6)	Each	4	3			12	225.57	2707.00
	Basic Rate	219.00							
	3% Area Weightage	6.57							
	Total	225.57							
46	Labour charges for Erection, Electrification and commissioning of Pump sets, including aligning and balancing of all items including supply and erection of two pair of supporting clamps, bore well caps, cable clips and water tight gland cable protectors, bolts, nuts, valve and gauges, tools and equipments etc., involved in the job as per specifications, with necessary tests as per specifications, with testing of as per instructions of engineer incharge of work. (PWD SR 2021-22 Vol-V Page No.163, Item No.38)	Job	4				4	6334.50	25338.00
	Basic Rate	6150.00							
	3% Area Weightage	184.50							
	Total	6334.50							
47	Labour charges for erection of outdoor type panel board and meter board units with all necessary materials and labour, tools and equipments including providing cement concrete foundation bed etc., complete as per specification, with testing of as per instructions of engineer incharge of work. (PWD SR 2021-22 Vol-V Page No.163, Item No.40)	Job	4				4	1390.50	5562.00
	Basic Rate	1350.00							
	3% Area Weightage	40.50							
	Total	1390.50							

SI No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
48	Supplying of 1.1KV LT UG cable XPLE or heat resistant PVC Insulated PVC extruded inner sheath armoured UG LT cable as per IS - 1554(Part-1) or IS-7098 Part-1, Armouring strip thickness in average +5% and resistivity 14ohms/kms(max) as per IS -3975 4 core 16sqmm (Ele SR 2019-20 P-No 40 I/No-6.4.4)	Rmtr	4	45.00			180.00	150.00	27000.00
49	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe/ stone pipe / on wall/ on pole as required 6 sqmm to 16 sqmm. (Ele SR OF 2019-20 P-No 41 I/No-6.5.1)	Rmtr	4	45.00			180.00	11.88	2139.00
50	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete cutting road surfaces(P.No - 41, I.No -6.6.3, KPWD Electrical SR 19-20)	Mtr	4	45.00			180.00	82.00	14760.00
51	Supplying and fixing of class A GI pipe on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class 40mm (P.No - 41, I.No -6.9.1, KPWD Electrical SR 19-20)	Mtr	4	4.00			16.00	335.00	5360.00
52	Earthing: Supplying and fixing and wiring earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts, nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia (PWD SR 2021-22 Vol-V Page No.164, Item No.45)	Job	4				4	3862.50	15450.00
	Basic Rate	3750.00							
	3% Area Weightage	112.50							
	Total	3862.50							
53	Providing,Supplying and fixing suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps,bolts,nuts and washers etc. with necessary materials and labour tools and equipments as per instructions of engineer incharge of work. 3½x6 Sqm (PWD SR 2021-22 Vol-V Page No.164, Item No.44.1)	Each	4				4	530.45	2122.00
	Basic Rate	515.00							
	3% Area Weightage	15.45							
	Total	530.45							
54	Supply and fixing polished wood board made of not less than 15mm thick plank on both sides of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws 20" x 20" x 2.5" (PWD Electrical SR 2022-23 Vol-VI Part-1 Page No.10, Item No.5.6.6)	Nos	4				4	315.00	1260.00
55	Providing,supplying to work site, Submersible Pump Set of 150mm dia suitable for bore well and confirming to IS 8034-2000;3Phase, SS Bowl & Impeller with Low volt Motor as per specifications,as per necessary ammendments and instructions of engineer incharge of work. 17.50 HP - 120 LPM @ 308 m = 26 STG Outlet Dia - 2.00" (PWD SR 2021-22 Vol-V Page No.161, Item No. 19.6)	Each	4				4	78963.00	315852.00
56	Supply and delivery of galvanized mild steel tubes of 6mtr standard length heavy duty (C Class) as per IS 1239 (Part-I) 1990 with latest amendments with ISI Mark (one end fitted with Heavy Duty collar and other end fitted with protective cover) (PWD SR 2021-22 Vol-V Page No.162, Item No.33.1)	Each	4	51.00			204.00	3141.50	640866.00
	Basic Rate	3050.00							
	3% Area Weightage	91.50							
	Total	3141.50							
57	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100 V as per IS-694:2010. 3C x 6 mm2 (PWD Electrical SR 2022-23 Vol-VI Page No.4, Item No.2.6.4)	Mtr	4	642.00			2568.00	242.00	621456.00
58	Supplying fully automatic star-delta starter unit push button type with suitable wires, 3 contactors, one adjustable thermal timer mounted on a common base plate held in steel enclosure for use on 400/440 V 3 phase and wired after fixing to the existing wooden board for motor Above 12.5 HP upto 25 HP (PWD Electrical SR 2022-23 Vol-VI Page No.10, Item No.5.2.2)	Nos	4				4.00	8640.00	34560.00
59	Supply and delivery at site of brand new best make gate valve as per IS 778/1984 with ISI Mark and as per its latest amendments Size 50 mm (PWD SR 2021-22 Vol-V Page No.162, Item No.27.1)	Each	4				4	1287.50	5150.00
	Basic Rate	1250.00							
	3% Area Weightage	37.50							



SI No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	Total	1287.50							
60	Supply and delivery at site of brand new best make non-return valve as per IS 778/1984 with ISI Mark and as per its latest amendments Size 50 mm (PWD SR 2021-22 Vol-V Page No.162, Item No.28.1)	Each	4				4.00	1313.25	5253.00
	Basic Rate	1275.00							
	3% Area Weightage	38.25							
	Total	1313.25							
61	Supply and delivery at site delivery of best indigenous brand new MCB (Miniature Circuit Breakers) of required capacity as per IS 88228/1978 and its latest amendments and with ISI Mark of 6/10/16/20/25/40 Amps with scalable box. (PWD SR 2021-22 Vol-V Page No.162, Item No.32)	per 3 Poles	4				4.00	1287.50	5150.00
	Basic Rate	1250.00							
	3% Area Weightage	37.50							
	Total	1287.50							
62	Earth work excavation for pipelines/cables by Manual means upto 600 mm trench width, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, including dressing of excavated surfaces, disposing off or leveling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m. Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering and lift upto 1.5 m including cost of labour, tools, usage& other appurtenances required to complete the work. (PWD SR 2021-22 Vol -I Pg No 6 item no 1.6.1)	Cum	4	425.00	0.60	0.75	765.00		
	For Connecting borewell						765.00	484.10	370337.00
	Sub total	470.00							
	Basic Rate	14.10							
	3% Area Weightage	484.10							
	Total								
63	Providing and installing at site of work 6 Kg/m2: 63mm(weight of pipe -0.662 kg) P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour charges and all lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. complete. (PWD SR 2021-22 Vol-V Page No.140, Item No.13)	mtr	4	425.00			1700.00		
	For Connecting borewell						1700.00	157.59	267903.00
	Sub total								
	Basic Rate	153.00							
	3% Area Weightage	4.59							
	Total	157.59							
64	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. Including cost of all labour complete as per specifications (PWD SR 2021-22 Vol -I Pg No 7 item no 1.10)	Cum	4	425.00	0.60	0.75	765.00		
	For Connecting borewell						765.00	125.66	96130.00
	Sub total	122.00							
	Basic Rate	3.66							
	3% Area Weightage	125.66							
	Total	Nos	4						
	BESCOM Charges						4	20000	80000.00

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
									80000.00
									Total of Other SR Items including GST Unit Rate
									139924700.00
									Total of RWS 21-22,Electrical SR 19-20,21-22,PWD SR 2018-19 And 2021-22 Items
									Sub Total
									140004700.00
									GST Charges (12% of estimated cost)
									16790964.00
									Total
									156795664.00
									DPR Charges (1% of estimated cost)
									1600000.00
									DPR Charges (1% of estimated cost)
									1600000.00
									Project management And Consultancy Charges(1% of estimated cost)
									4336.00
									Miscellenious and rounding
									Total Amount
									160000000.00
									RUPEES SIXTEEN CRORE ONLY

CERTIFICATE:

- 1) The work spot has been inspected and found to be necessary
- 2) The work spot comes under B.B.M.P
- 3) The provisions made in the estimate are necessary and minimum
- 4) The estimate is based on C.S.R of 2018-2019, PWD 2021-2022, RWS-21-22 KPTCL-21-22 Issue rates and Data Rates.

[Signature]
Assistant Engineer
BBMP

[Signature]
Assistant Executive Engineer
BBMP

[Signature]
Executive Engineer
BBMP



Technical Function
Accorded For *RS. 1600.00 lakhs*
Head of A/C *P. 3877*
CER NO *31* Dt: *21/6/22*

Administrative Approval
Accorded For *RS. 1600.00 lakhs*
Head of A/C *P. 3877*
CER NO *05* Dt: *18/8/2022*

[Signature]
E.E. (Project)

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	Total of Other SR Items including GST Unit Rate								80000.00
	Total of RWS 21-22,Electrical SR 19-20,21-22,PWD SR 2018-19 And 2021-22 Items								139924700.00
	Sub Total								140004700.00
	GST Charges (12% of estimated cost)								16790964.00
	Total								156795664.00
	DPR Charges (1% of estimated cost)								1600000.00
	Project management And Consultancy Charges(1% of estimated cost)								1600000.00
	Miscellenious and rounding								4336.00
	Total Amount								160000000.00
	RUPEES SIXTEEN CRORE ONLY								

CERTIFICATE:

- 1) The work spot has been inspected and found to be necessary
- 2) The work spot comes under B.B.M.P
- 3) The provisions made in the estimate are necessary and minimum
- 4) The estimate is based on C.S.R of 2018-2019, PWD 2021-2022, RWS-21-22 KPTCL-21-22 Issue rates and Data Rates.

[Signature]
Assistant Engineer
BBMP

[Signature]
Assistant Executive Engineer
BBMP

[Signature]
Executive Engineer
BBMP



Technical sanction
Accorded For *RS. 1600.00 lakhs*
Head of A/C *P-3877*
CER NO : *31* Dt: *21/6/22*

[Signature]

Administrative Approval
Accorded For *RS. 1600.00 lakhs*
Head of A/C *P-3877*
CER NO : *05* Dt: *18/8/2022*

[Signature]
E.E. (Project)